

GENERAL LANDSCAPE SPECIFICATIONS

1. **PLANTS** - Planting to be carried out with horticultural best practices. All species are to conform with specified species, sizes, quantities and locations as indicated on planting plans, unless otherwise indicated by the landscape architect. In the case of required species substitution, approval must be sought out by the landscape architect before ordering of stock. Plant stock is to be vigorous and undamaged, appropriately established for the specified pot size, of good form, not root bound and be free of diseases, pests and weeds. Plant placement to be confirmed by the landscape architect unless otherwise stated.
2. **FERTILISING** - At the time of planting, an application of a suitable fertiliser and conditioner, per the plant species and soil media, are to be applied as per the manufacturers specifications. Slow and quick release fertilisers are to be applied to lawn areas and well watered in at time of planting.
3. **POTS** - Apply Mapei acrylic waterproofing membrane to internal walls and floor of all pots. Irrigation lines to be installed through base of pots. Install double layer of drainage cell panels to base of pots. Geofabric to be laid above drainage cells. Void filling media to be applied through central zone of pots where suitable. Planting media to be a blend of Decco premium potting mix (70%), vermiculite (15%) and peat moss (15%) with an application of slow-release fertiliser.

GARDENS IN NATURAL GROUND

1. **EXCAVATION** - All garden areas are to be trimmed to a minimum depths of 220mm below finished levels, allowing for the application of top soil and mulch meeting with finished surface levels unless otherwise specified.
2. **WEEDS AND EXISTING VEGETATION** - All weeds and unwanted plants are to be thoroughly removed, including roots and rhizomes. Controlled application of herbicides to be used where required with appropriate best practices in accordance with manufacturer instructions. Care must be taken to ensure all trees to be retained are not damaged in accordance with Australian Standard AS 4970-2009. All trees to be removed shall be stump ground.
2. **SOIL PREPARATION** - All garden areas are to have building materials, crushed rock and any other material restrictive to plant growth removed. All garden area subsoils are to be cultivated and aerated to a depth of 200mm, with an application of gypsum applied to all heavy clay areas at the rate of 1.5kg per sq. meter.
3. **TOP SOIL** - All garden areas to have imported 5 way organic garden soil, with a neutral pH, laid over prepared subsoils to a minimum depth of 150mm. All imported topsoil is to be free from rubble, weeds and other materials damaging to plant growth.
4. **MULCH** - All garden areas to have an even 50mm spread layer of 'Surecrop' compost applied unless otherwise specified. Mulch to be kept back from plants stems to prevent collar rot.
8. **GARDEN BEDS** - Cultivate to a depth of 125mm and import 150mm layer of 5 way organic topsoil / compost blend. Ensure stormwater wastes are installed in all planters. In accordance with Civil Engineer's specifications, lay non-shrink screed with 1 in 50 falls to wastes. Apply waterproofing membrane to buried surfaces in accordance with waterproofing specialist's specifications. Line floors of planters with AG drainage cell panels and walls with black core flute protective boards fill planters with potting mix (75%), blended with 'Surecrop' compost (25%). Both available from Fulton Garden supplies. Spread layer of 'Surecrop' compost after plant installation. All beds to be irrigated as per irrigation specialist specification.

GARDENS ABOVE SLAB

1. **WATER PROOFING** - Apply waterproofing membrane to all internal planter surfaces.
2. **WATERPROOFING PROTECTION** - LPDE layer at minimum 200 microns for horizontal surfaces, and Confluite Protection Board Layer to vertical surfaces is to be applied over waterproofing membrane on gardens installed directly above or against roof or building structural surfaces.
3. **DRAINAGE** - Install Atlantis Floorcell 20 drainage cell laid as a base above waterproofing.
4. **GEOFABRIC** - Bidin A14-A24 Geofabric to be laid above drainage cell.
5. **VOID FILLER** - Atlantis Structural Void filling media is to be applied through planters where necessary, as specified in typical details.
5. **SOIL** - Fytogreen Hydrocell 40 Lightweight Planter Media to depths as specified in typical details. Garden beds are to be filled with the required soil amounts a minimum of 2 months prior to the addition of plants and mulch, with irrigation activated a minimum 2 times a week during this period. Soil settlement to be observed at the time of planting, with replenishment to the appropriate height where required.
6. **MULCH** - Selected Gravel Screenings as specified in material schedule, to a minimum depth of 50mm.
7. **IRRIGATION** - Drip Irrigation to be installed below mulch, or 50mm beneath finished garden surface.

PLANT SCHEDULE

CODE	QTY	BOTANICAL NAME	COMMON NAME	*HEIGHT	*SPREAD	SIZE	REMARKS
Trees							
Cec	2	Cercis canadensis	Eastern Redbud	6 m	4 m	45Ltr	MIS 25
Pic	1	Pistacia chinensis	Chinese Pistachio	8 m	6 m	45Ltr	
Ulp	1	Ulmus parvifolia	Chinese Elm	18 m	15 m	45Ltr	
Shrubs							
Cob	11	Correa baeuerlenii	Chef's Cap Correa	1.5 m	1.5 m	300 mm	
Cogl	15	Correa glabra	Rock Correa	1.5 m	1.5 m	300 mm	
CorP	50	Correa reflexa x pulchella	Dusky Bells	1.5 m	1.0 m	300 mm	
Pit	6	Pittosporum tobira 'Miss Muffet'	Miss Muffet	1 m	1.2 m	140 mm	
Perennials							
Grasses							
Dit	17	Dianella tasmanica	Tasman Flax Lily	0.7m	0.7m	140 mm	
Dita	17	Dianella tasmanica 'Emerald Arch'	Native Flax	0.4 m	0.4 m	140 mm	
Lime	105	Liriope muscari 'Emerald Falls'	Emerald Falls Liriope	0.3 m	0.5 m	140 mm	
Lole	457	Lomandra labilli 'Evergreen Baby'	Evergreen Baby Lomandra	0.5 m	0.5 m	140 mm	
LoIN	123	Lomandra longifolia 'Nyalia'	Lomandra Nyalia	0.8 m	0.8 m	140 mm	
Groundcovers							
Brm	18	Brachycome multifida	'Pacific Cloud'	0.3 m	.3 m	140 mm	
CagC	33	Casuarina glauca 'Cousin It'	Casuarina 'Cousin It'	0.2 m	1.5 m	140 mm	
Myop	49	Myoporum parvifolium	Creeping Boobialla	.2 m	1.0 m	140 mm	
Vih	41	Viola hederacea	Native Violet	0.15 m	1.5 m	140mm	
Succulents							
Climbers							
Paq	6	Parthenocissus quinquefolia	Virginia creeper		CLIMBER	140mm	---
Ferns / Shade Perennials							
Bln	13	Blechnum nudum	Fishbone Water Fern	0.8 m	0.8 m	140 mm	MIS 25
Pop	14	Polystichum proliferum	Soft Shield Fern	.8m	.8m	140mm	
Total:	979				* = maintained		

REFER DRAWING SD-5.03- PLANTING PLAN - SOUTH

REFER DRAWING SD-5.03- PLANTING PLAN - SOUTH

1 Planting Plan - North
Scale: 1:100