

## GENERAL LANDSCAPE SPECIFICATIONS

1. PLANTS - Planting to be carried out with horticultural best practices. All species are to conform with specified species, sizes, quantities and locations as indicated on planting plans, unless otherwise indicated by the landscape architect. In the case of required species substitution, approval must be sought out by the landscape architect before ordering of stock. Plant stock is to be vigorous and undamaged, appropriately established for the specified pot size, of good form, not root bound and be free of diseases, pests and weeds. Plant placement to be confirmed by the landscape architect unless otherwise stated. 2. FERTILISING - At the time of planting, an application of a suitable fertiliser and conditioner, per the plant species and soil media, are to be applied as per the manufacturers specifications. Slow and quick release fertilisers are to be applied to lawn areas and well watered in at time of planting. 3. POTS • Apply Mapei acrylic waterproofing membrane to internal walls and floor

of all pots. Irrigation lines to be installed through base of pots. Install double layer of drainage cell panels to base of pots. Geofabric to be laid above drainage cells. Void filling media to be applied through central zone of pots where suitable. Planting media to be a blend of Debco premium potting mix (70%), vermiculite (15%) and peat moss (15%) with an application of slow-release fertiliser.

## GARDENS IN NATURAL GROUND

1. EXCAVATION - All garden areas are to be trimmed to a minimum depths of 220mm below finished levels, allowing for the application of top soil and mulch meeting with finished surface levels unless otherwise specified. 2. WEEDS AND EXISTING VEGEATION- All weeds and unwanted plants are to be thoroughly removed, including roots and rhizomes. Controlled application of herbicides to be used where required with appropriate best practices in accordance with manufacturer instructions. Care must be taken to ensure all trees to be retained are not damaged in accordance with Australian Standard AS 4970-2009. All trees to be removed shall be stump ground. 2. SOIL PREPARATION - All garden areas are to have building materials, crushed rock and any other material restrictive to plant growth removed. All garden area subsoils are to be cultivated and aerated to a depth of 200mm, with an application of gypsum applied to all heavy clay areas at the rate of 1.5kg per sq. meter 3. TOP SOIL - All garden areas to have imported 5 way organic garden soil, with a neutral pH, laid over prepared subsoils to a minimum depth of 150mm. All

4. MULCH - All garden areas to have an even 50mm spread layer of 'Surecrop' compost applied unless otherwise specified. Mulch to be kept back from plants stems to prevent collar rot.

imported topsoil is to be free from rubble, weeds and other materials damaging

8. GARDEN BEDS • Cultivate to a depth of 125mm and import 150mm layer of 5 way organic topsoil / compost blend. Ensure stormwater wastes are installed in all planters, in accordance with Civil Engineer's specifications, lay non-shrink screed with 1 in 50 falls to wastes. Apply waterproofing membrane to buried surfaces in accordance with waterproofing specialist's specifications. Line floors of planters with AG drainage cell panels and walls with black core flute protective boards fill planters with potting mix (75%), blended with 'Surecrop' compost (25%). Both available from Fulton Garden supplies•Spread layer of 'Surecrop' compost after plant installation. All beds to be irrigated as per irrigation specialist

## GARDENS ABOVE SLAB

specification.

1. WATER PROOFING - Apply waterproofing membrane to all internal planter

2. WATERPROOFING PROTECTION - LPDE layer at minimum 200 microns for to be applied over waterproofing membrane on gardens installed directly above or against roof or building structural surfaces.

3. DRAINAGE - Install Atlantis Flocell 20 drainage cell laid as a base above

waterproofing. 4. GEOFABRIC - Bidim A14-A24 Geofabric to be laid above drainage cell. 5. VOID FILLER - Atlantis Structural Void filling media is to be applied through planters where necessary, as specified in typical details.

5. SOIL- Fytogreen Hydrocell 40 Lightweight Planter Media to depths as specified in typical details. Garden beds are to be filled with the required soil amounts a minimum of 2 months prior to the addition of plants and mulch, with irrigation activated a minimum 2 times a week during this period. Soil settlement to be observed at the time of planting, with replenishment to the appropriate height where required.

minimum depth of 50mm. 7. IRRIGATION - Drip Irrigation to be installed below mulch, or 50mm beneath finished garden surface.

6. MULCH - Selected Gravel Screenings as specified in material schedule, to a

## PLANT SCHEDULE - SOUTH

CODE	QTY	BOTANICAL NAME	COMMON NAME	*HEIGHT	*SPREAD	SIZE	REMARKS
Trees							
Cec	8	Cercis canadensis	Eastern Redbud	6 m	4 m	45Ltr	MIS 25
Pic	5	Pistacia chinensis	Chinese Pistachio	8 m	6 m	45Ltr	
Ulp	1	Ulmus parvifolia	Chinese Elm	18 m	15 m	45Ltr	
Shrubs							
Cob	3	Correa baeuerlenii	Chef's Cap Correa	1.5 m	1.5 m	300 mm	
Cogl	18	Correa glabra	Rock Correa	1.5 m	1.5 m	300 mm	
CorP	56	Correa reflexa x pulchella	Dusky Bells	1.5 m	1.0 m	300 mm	
Dov	6	Dodonaea viscosa subsp. spatulata	Hop Bush	2 m	2 m	300 mm	
Pit	27	Pittosporum tobira 'Miss Muffet'	Miss Muffet	1 m	1.2 m	140 mm	
Perenni	als						
Acm	4	Acanthus Mollis	Oyster plant	0.8 m	0.8 m	140 mm	
Grasses	;						
Dit	9	Dianella tasmanica	Tasman Flax Lily	0.7m	0.7m	140 mm	
Dita	117	Dianella tasmanica 'Emerald Arch'	Native Flax	0.4 m	0.4 m	140 mm	
Lime	164	Liriope muscari 'Emerald Falls'	Emerald Falls Liriope	0.3 m	0.5 m	140 mm	
Lole	476	Lomandra labill 'Evergreen Baby'	Evergreen Baby Lomandra	0.5 m	0.5 m	140 mm	
LoIN	161	Lomandra longifolia 'Nyalla'	Lomandra Nyalla	0.8 m	0.8 m	140 mm	
Phte	9	Phormium tenax	New Zealand Flax	1.5m	1.0m	140 mm	
Ground	covers						
Brm	80	Brachycome multifida	'Pacific Cloud'	0.3 m	.3 m	140 mm	
CagC	20	Casuarina glauca 'Cousin It'	Casuarina 'Cousin It'	0.2 m	1.5 m	140 mm	
Муро	25	Myoporum parvifolium	Creeping Boobialla	.2 m	1.0 m	140 mm	
Succule	nts						
Climber	s						
Paq	10	Parthenocissus quinquefolia	Virginia creeper		CLIMBER	140mm	
Ferns /	Shade I	Perennials					
Bln	4	Blechnum nudum	Fishbone Water Fern	0.8 m	0.8 m	140 mm	MIS 25
Pop	7	Polystichum proliferum	Soft Shield Fern	.8m	.8m	140mm	
Total:	1210			* = maintained			



Acre

These are conceptual drawings only. Acre Landscape Architecture Studio will not be held responsible for any structural works constructed from these drawings. All dimensions to be confirmed on site by contractor prior to commencement of works.