

TCCS STANDARD CONDITIONS

The following general conditions will apply, as appropriate, for the Works and use of Territory land and potential impacts on TCCS services in addition to any specific conditions imposed in the DA Notice of Decision. In accordance with the Public Unleased Land Act 2013 no Works are to be undertaken without the approval of the TCCS. Such approval must be obtained from the relevant Senior Director of the TCCS Development Coordination Branch by the ways of (1) a Building Approval; or (2) a Letter of Early Works Approval, or (3) a Letter of Design Review prior to the commencement of any Works.

Early Works Approval

Early works typically include site preparation and establishment, implementation of temporary traffic management plan and landscape management and protection plan and earthworks / excavations. Early Works do not include any building works or offsite works.

Fees and charges will apply for Early Works Approval as per TCCS "GEN-06 - Submissions and Inspections Guideline Principles and Related Fees and Charges for TCCS and Industry".

Design Review

In order to obtain the Letter of Design Review, fully detailed drawings (civil, landscape) prepared by suitably qualified persons for all off-site works including roads, driveways, footpaths, street lighting, stormwater, landscaping (and any other issues that may be found by audit of the plans) and a design report in accordance with TCCS "REF-06 - Requirements for Design Review Submissions", must be certified by a Chartered Engineer/Landscape Architect and submitted to the relevant Senior Director of the TCCS Development Coordination Branch.

Waste and Recycling Management Plan (WRMP) review

*Unless a fully completed WRMP and mandatory submission documents (in accordance with 2019 Development Control Code for Best Practice Waste Management in the ACT) have been submitted and endorsed by TCCS at the DA stage, then **noncompliance will not be supported**. A **performance-based-application** can only be considered if a pre-application meeting is held (before a DA is submitted) and TCCS provides the Applicant with a **letter of endorsement** which is presented to EPSDD at the DA stage.*

Operational Acceptance/Soft Landscape Consolidation Commencement

On completion of the Works, a Certificate of Operational Acceptance is required from the relevant Senior Director of the TCCS Development Coordination Branch, prior to the issuance of a Certificate of Occupancy.

Where required, a Certificate of Soft Landscape Consolidation Commencement must also be obtained from the relevant Senior Director of the TCCS Development Coordination Branch for the placement of soft landscape works on consolidation.

A Chartered Engineer/Landscape Architect must certify compliance with TCCS "REF 08 - Requirements for Works as Executed Quality Records Requirements" when the request for Operational Acceptance and/or Consolidation Commencement is made to the relevant Senior Director of the TCCS Development Coordination Branch on completion of all Works.

Final Acceptance/Soft Landscape Handover

A Certificate of Final Acceptance for all civil and hard landscape works must be obtained from the relevant Senior Director of the TCCS Development Coordination Branch at the end of the required Defects Liability Period (DLP) as noted in the Certificate of Operational Acceptance.

A Certificate of Soft Landscape Handover for all soft landscape works must be obtained from the relevant Senior Director of the TCCS Development Coordination Branch at the end of the required Consolidation Period as noted in the Certificate of Consolidation Commencement.

Temporary Traffic Management (TTM)

A TTM plan approval from the Manager of TCCS Traffic Management & Safety, Roads ACT, must be obtained prior to commencement of Works. This plan must be prepared by a suitably qualified person and address, as a minimum, measures to be employed at all times during construction activities to manage all traffic, including construction and regular traffic in and around the site, provision of safe pedestrian movement around the site, the provision of parking for construction workers, and associated temporary traffic control devices.

Landscape Management & Protection Plan (LMPP)

LMPP approval must be obtained from the relevant Senior Director of the TCCS Development Coordination Branch or the delegated authority. During construction, all existing vegetation (trees, shrubs and grass) located within the verge and unleased Territory land immediately adjacent to the development must be managed, protected and maintained in accordance with the approved LMPP. This plan must be implemented before the commencement of any Works, including demolition on the site, and must be in accordance with TCCS "REF 04 - Requirements for the Protection of Public Landscape Assets Adjacent to Development Works".

Use of verges or other unleased Territory land

In accordance with the Public Unleased Land Act 2013, road verges and other unleased Territory land must not be used for carrying out of Works, including storage of materials or waste, without prior approval from TCCS. If required, a license can be obtained from TCCS Licensing and Compliance.

Repair of damage to public assets

Before the Works commence TCCS must be notified of any existing damage to public assets via a Dilapidation Report. The applicant/lessee is held responsible for repairing any damage to ACT Government's assets, caused by the development activities, to the satisfaction of TCCS. If a Dilapidation Report is not provided, any pre-existing damage must also be repaired at the applicant/lessee's cost.

Notice of Commencement of construction

A Notice of Commencement for the Works within Unleased Territory Land must be submitted to TCCS one week prior to the commencement of Works. The notice must also include the confirmation of any protective measures installed in accordance with the approved LMPP and the programmed implementation of TTM.